

of the Commencement Date and prior to the commencement of any demolition or construction work. The Contractor will also establish the levels of these areas.

The survey shall be undertaken in conjunction with the Engineer. The originals of the survey report and the photographs and negatives shall be handed over to the Engineer within two (2) weeks of the completion of the survey, one (1) copy retained by the Contractor, and one (1) copy handed over to the Employer at the same time.

7.4 Existing Services

The Contractor shall undertake all the necessary requirements to identify any existing services that are/potential to be impacted by the associated works in the Contract.

Where works are to be undertaken in areas containing existing services, the Contractor shall establish their precise location by hand-digging trenches or by other suitable means such as electronic scanning before laying any adjacent new service. The Contractor shall provide such information regarding existing services to the Engineer and shall include such details on his record and as-built drawings.

The Contractor shall liaise with all service providers to confirm and identify all existing services information. In the event of unknown services being discovered during the carrying out of the Works, the Contractor shall immediately inform the Engineer in writing. Payment for diverting or sealing off and abandoning any of these services if necessary or working around the same will only be made where the proviso to (Information and Inspection) the Conditions of Contract applies and even then, only against certified records and subject to the prior authorization of the Engineer with the consent of the Employer. The Contractor shall locate dimensionally on its as-built drawings all services encountered on the Site.

7.5 Third Party Approvals and Notices

The Contractor's responsibility shall be to carry out and complete the whole of the Works to comply as a minimum with the requirements of each and every relevant statutory, regulatory and utilities authorities.

Should the Contractor for any reason whatsoever cause such approvals, permits, consents, etc to be withdrawn, the Contractor shall be fully responsible for their reinstatement or re-issuance, irrespective of whether such were originally procured by the Employer.

The Contractor shall not commence any element of the project including but not limited to; demolition, excavation, filling, construction or any other works until he has obtained written approval from the relevant statutory, regulatory and utilities authorities, and a copy of that approval has been submitted to the Engineer.

The Contractor's general obligations shall include, without limitation:

- a. obtaining the necessary approvals/ permits/ consents, etc for excavation works;
- b. the submission of the Contractor's temporary works designs and shop drawings to the relevant authorities and Engineer, obtaining both approvals as applicable;
- c. complying with the relevant requirements of the Employer's environmental commitments and any future requirements included within the updated environmental approvals with respect to the construction of the works;